

4' SA Standard Features

16" On Center Cross Members	.080 Polycore	ST175 13" Radial Tires	2000 lb Straight Leaf Spring Axle
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	Flat 4 Pigtail On Units Without Brakes
16" On Center Sidewalls	Interior Height 48" (4')	Galvalume Roof	E-Z Lube Hubs
2000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	V-Nose w/12" Stoneguard	Rear Door Handle
2" Coupler	3/8" Plywood Walls	Therma-Ply Ceiling	Full LED Light Pkg. Incl. Rear Loading Light
3" Steel Tube Main Frame	Single Rear Door		

5' SA Standard Features

16" On Center Cross Members	.080 Polycore	ST205 15" Radial Tires	2990 lb Drop Leaf Spring Axle
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	Flat 4 Pigtail On Units Without Brakes
16" On Center Sidewalls	Interior Height 60" (5')	Galvalume Roof	E-Z Lube Hubs
2000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Wall Vents	Ramp Door w/ Flap & (2) Handles
2" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Door Hold Back
3" Steel Tube Main Frame	(1) 12v Dome Light	Therma-Ply Ceiling	Full LED Light Pkg. Incl. Rear Loading Light

6' SA Standard Features

16" On Center Cross Members	.080 Polycore	ST205 15" Radial Tires	2990 lb Drop Leaf Spring Axle
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	Flat 4 Pigtail On Units Without Brakes
16" On Center Tubing Sidewalls	Interior Height 78" (6'6")	Galvalume Roof	E-Z Lube Hubs
5000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Wall Vents	Ramp Door w/ Flap & (2) Handles
2" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Door Hold Back
32" Side Door w/ Flush Lock & Barlock	(1) 12v Dome Light	Therma-Ply Ceiling	Full LED Light Pkg. Incl. Rear Loading Light
3" Steel Tube Main Frame (4" Steel Tube Main Frame on 14')			Loading Light Above Side Door

6' TA Standard Features

16" On Center Cross Members	.080 Polycore	ST205 15" Radial Tires	3500 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	7 Way Pigtail & E-Z Lube Hubs
16" On Center Tubing Sidewalls	Interior Height 78" (6'6")	Galvalume Roof	Ramp Door w/ Flap & (2) Handles
5000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Wall Vents	Door Hold Back
2 5/16" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Full LED Light Pkg. Incl. Rear Loading Light
4" Steel Tube Main Frame	(1) 12v Dome Light	Therma-Ply Ceiling	Loading Light Above Side Door
32" Side Door w/ Flush Lock & Barlock (24" Side Door on 10')			

7' SA Standard Features

16" On Center Cross Members	.080 Polycore	ST205 15" Radial Tires	2990 lb Drop Leaf Spring Axle
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	Flat 4 Pigtail On Units Without Brakes
16" On Center Tubing Sidewalls	Interior Height 84" (7')	Galvalume Roof	E-Z Lube Hubs
5000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Vents	Ramp Door w/ Flap & (2) Handles
2-5/16" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Door Hold Back
36" Side Door w/ Flush Lock & Barlock	(1) 12v Dome Light	Therma-Ply Ceiling	Full LED Light Pkg. Incl. Rear Loading Light
4" Steel Tube Main Frame			Loading Light Above Side Door

7' TA Standard Features

16" On Center Cross Members	.080 Polycore	ST205 15" Radial Tires	3500 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	7 Way Pigtail & E-Z Lube Hubs
16" On Center Tubing Sidewalls	Interior Height 84" (7')	Galvalume Roof	Ramp Door w/ Flap & (2) Handles
5000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Vents	Door Hold Back
2 5/16" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Full LED Light Pkg. Incl. Rear Loading Light
36" Side Door w/ Flush Lock & Barlock	(1) 12v Dome Light	Therma-Ply Ceiling	Loading Light Above Side Door
24" Side Door w/ Flush Lock & Barlock on 10'	Models 14' & Under Include	-4" Tube Steel Main frame	

8' TA Standard Features

16" On Center Cross Members	.080 Polycore	ST205 15" Radial Tires	3500 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	7 Way Pigtail & E-Z Lube Hubs
16" On Center Tubing Sidewalls	Interior Height 84" (7')	Galvalume Roof	Ramp Door w/Flap & (2) Handles
5000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Vents	Door Hold Back
2 5/16" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Full LED Light Pkg. Incl. Rear Loading Light
36" Side Door w/ Flush Lock & Barlock	(2) 12v Dome Light	Therma-Ply Ceiling	Loading Light Above Side Door
6" Tube Steel Main Frame			

8.5' UP TO 24'TA Standard Features

		(4) 5000 lb D-Rings	
16" On Center Cross Members	.080 Polycore	ST205 15" Radial Tires	3500 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	7 Way Pigtail & E-Z Lube Hubs
16" On Center Tubing Sidewalls	Interior Height 84" (7')	Galvalume Roof	No Show Beavertail on 16' and above
5000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Vents	Heavy Duty Ramp Door w/Flap & (2) Handles
2 5/16" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Door Hold Back
36" Side Door w/ Flush Lock & Barlock	(2) 12v Dome Light	ATP Covered Stepwell	Full LED Light Pkg. Incl. Rear Loading Light
6" Tube Steel Main Frame		Therma-Ply Ceiling	Loading Light Above Side Door

8.5x26+ TA Standard Features

		(4) 5000 lb D-Rings	6000 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Cross Members	.080 Polycore	ST225 15" Radial Tires	w/Triple Tube Tongue & E-Z lube Hubs
16" On Center Roof Members	Semi-Screwed Exterior	ATP Fenders	7 Way Pigtail No Show Beavertail
16" On Center Tubing Sidewalls	Interior Height 84" (7')	Galvalume Roof	Heavy Duty Ramp Door w/Flap & (2) Handles
5000 lb A-Frame Jack w/ Sand Foot	3/4" Plywood Floors	Plastic Side Vents	Door Hold Back
2 5/16" Coupler	3/8" Plywood Walls	V-Nose w/24" Stoneguard	Full LED Light Pkg. Incl. Rear Loading Light
36" Side Door w/ Flush Lock & Barlock	(2) 12v Dome Light	ATP Covered Stepwell	Loading Light Above Side Door
8" Tube Steel Main Frame	Therma-Ply Ceiling	*30'+ One Piece Roof, Double Tube Main Frame Over Axles & Straps Across Side Walls	

8.5' Triple Standard Features

	.080 Polycore	(4) 5000 lb D-Rings	6000 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Cross Members	Semi-Screwed Exterior	ST225 15" Radial Tires	w/Triple Tube Tongue & E-Z lube Hubs
16" On Center Roof Members	Interior Height 84" (7')	ATP Fenders	7 Way Pigtail No Show Beavertail
16" On Center Tubing Sidewalls	3/4" Plywood Floors	One Piece Aluminum Roof	Heavy Duty Ramp Door w/Flap & (2) Handles
5000 lb A-Frame Jack w/ Sand Foot	3/8" Plywood Walls	Plastic Side Vents	Door Hold Back
2 5/16" Coupler	(2) 12v Dome Light	V-Nose w/24" Stoneguard	Full LED Light Pkg. Incl. Rear Loading Light
36" Side Door w/ Flush Lock & Barlock	Therma-Ply Ceiling	ATP Covered Stepwell	Loading Light Above Side Door
8" Tube Steel Main Frame - Doubled Over Axles		Straps Across Side Walls	Bogey Wheels (Pair)

***GVWR DE-RATED TO: 15,200 TO GET FULL 18,000 GVWR MUST ADD 16" 6-LUG**

GN 28-32TA Standard Features			
	.080 Polycore	(4) 5000 lb D-Rings	6000 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Cross Members	Semi-Screwed Exterior	ST225 15" Radial Tires	7 Way Pigtail & E-Z Lube Hubs
16" On Center Roof Members	Interior Height 84" (7')	ATP Fenders	Heavy Duty Ramp Door w/Flap & (2) Handles
16" On Center Tubing Sidewalls	3/4" Plywood Floors	One Piece Roof	Door Hold Back
Dual Hydraulic Landing Gear	3/8" Plywood Walls	Plastic Side Vents	Full LED Light Pkg. Incl. Rear Loading Light
GN Adjustable 2 5/16" Coupler	(3) 12v Dome Light	8' Riser Deck w/ ATP & (2) Ac	Loading Light Above Side Door
48" Side Door w/ Flush Lock & Barlock	Therma-Ply Ceiling	ATP Covered Stepwell	
8" Tube Steel Main Frame - Doubled Over Axles		Straps Across Side Walls	

GN 34-52 TTA Standard Features			
	.080 Polycore	(4) 5000 lb D-Rings	6000 lb Drop Leaf Spring Axles w/ Electric Brakes
16" On Center Cross Members	Semi-Screwed Exterior	ST225 15" Radial Tires	7 Way Pigtail & E-Z Lube Hubs
16" On Center Roof Members	Interior Height 84" (7')	ATP Fenders	Heavy Duty Ramp Door w/Flap & (2) Handles
16" On Center Tubing Sidewalls	3/4" Plywood Floors	One Piece Roof	Door Hold Back
Dual Hydraulic Landing Gear	3/8" Plywood Walls	Plastic Side Vents	Full LED Light Pkg. Incl. Rear Loading Light
GN Adjustable 2 5/16" Coupler	(3) 12v Dome Light	8' Riser Deck w/ ATP & (2) Ac	Loading Light Above Side Door
48" Side Door w/ Flush Lock & Barlock	Therma-Ply Ceiling	ATP Covered Stepwell	
8" Tube Steel Main Frame - Doubled Over Axles		Straps Across Side Walls	

***GVWR DE-RATED TO: 15,200 TO GET FULL 18,000 GVWR MUST ADD 16" 6-LUG**